

Line Sets

You will save time when you use our Line Sets because they are assembled especially for our units. They are convenient, inexpensive and they contain everything you need for quick and easy installation.

Line Set Model No.	Tili Ductless Model	Liquid Line	Vapour Line	Length	Dimensions Inches
TCP09L15	TKU(H)09VM	1/4"	3/8"	15	22x22x2.95
TCP12/18L15	TKU(H)12VM TKU(H)18WM	1/4"	1/2"	15	22x22x2.95
TCP24L15	TKU(H)24WM	3/8"	5/8"	15	24x24x3
TCP09L25	TKU(H)09VM	1/4"	3/8"	25	22x22x2.95
TCP12/18L25	TKU(H)12VM TKU(H)18WM	1/4"	1/2"	25	22x22x2.95
TCP24L25	TKU(H)24WM	3/8"	5/8"	25	24x24x3
TCP09L50	TKU(H)09VM	1/4"	3/8"	50	22x22x2.95
TCP12/18L50	TKU(H)12VM TKU(H)18WM	1/4"	1/2"	50	22x22x2.95
TCP24L50	TKU(H)24WM	3/8"	5/8"	50	24x24x3



Details: All line sets include copper lines with both liquid and suction lines insulated with 1/4" rubber. Each set is equipped with flare nuts on both ends. Other accessories also in the set include: power cable, extended condensate drainage flexible pipe, binding tapes, etc.



Guaranteed Quality

Every air conditioner Tili makes goes through an extensive array of over 37 quality tests on the production line. We use state-of-the-art systems such as helium spectrum and ultra sonic calibration for leak detection.

We test everything thoroughly; electronics, copper tubing, compressors, heat exchangers, plastic, even the paint. Nothing is left out to ensure the finished product is a quality machine.

Additionally, we continuously fine-tune our manufacturing process by tracking customer feedback. After many years of refinement, we have established ourselves globally as a premium manufacturer of high-quality products.

Precision Manufacturing

